

*Michael R. Wigley, AIA, LEED AP  
W. Zachary Crouch, P.E.  
Michael E. Wheedleton, AIA, LEED GA  
Jason P. Loar, P.E.  
Ring W. Lardner, P.E.  
Jamie L. Sechler, P.E.*

**PRICKETT WINDOW REPLACEMENT  
DELAWARE HOSPITAL FOR THE CHRONICALLY ILL  
SMYRNA, DELAWARE 19977  
CONTRACT #MC3514000061  
DBF #0586B037.Z01**

**AUGUST 10, 2021**

**ADDENDUM NO. 6**

The following items shall become a part of the contract documents. Contractor must acknowledge receipt of this addendum on the Bid Form. Failure to do so may subject the Bidder to disqualification.

- Item No. 1 Clarification: Detail K12/A2.1: Locations are not known, contractor shall assume (4) locations per floor.
- Item No. 2 Foam Insulation is required to fill gaps at all windows.
- Item No. 3 As noted on the drawings, the metal window sills are to remain and new poplar sills will be installed on top.
- Item No. 4 Clarification: Detail F9/A2.1: This detail refers to all windows.
- Item No. 5 Exterior moulding is specified as a 3-1/2" bed moulding.
- Item No. 6 The interior trim thickness shall be 5/4" inch.
- Item No. 7 The interior trim widths shall be 6 inches for the jamb and head and 4 inches for the face of the wall.
- Item No. 8 Clarification: Detail F6/A2.1 is a typical jamb detail and Detail K6/A2.1 does not apply to this project.
- Item No. 9 Clarification: The purpose of the unit prices is to get a cost per window to remove and replace as detailed on the drawings.
- Item No. 10 The door shown on Window Type D is part of the aluminum storefront system. Door hardware shall include: Push/pull, continuous hinge, closer, weatherstripping, thumb latch lock, and threshold.

**END OF ADDENUM**