

Delaware Department of Transportation
PROPOSAL FOR

Letting ID: 20211102
11/02/2021 02:00:00 PM

Contract ID: T202180102
Call: 004

BID TYPE:
(Enter a Bid Type, otherwise bid will be considered Regular)

Submitted by

Conventional Builders, Inc
846 School Street

Houston, DE 19954

Line Number	Item Number	Quantity	Unit	Unit Price	Extension Price
Section 0001					
General					
0010	201000	1.00	LS		
					CLEARING AND GRUBBING
0020	202000	2236.00	CY		
					EXCAVATION AND EMBANKMENT
0030	204000	16.00	CY		
					TEST HOLE
0040	209001	350.00	CY		
					BORROW, TYPE A
0050	209006	50.00	CY		
					BORROW, TYPE F
0060	211000	1.00	LS		
					REMOVAL OF STRUCTURES AND OBSTRUCTIONS
0070	211001	245.00	SY		
					REMOVAL OF PORTLAND CEMENT CONCRETE PAVEMENT, CURB AND SIDEWALK
0080	301001	498.00	CY		
					GABC
0090	401005	323.00	TON		
					SUPERPAVE TYPE C, PG 64-22 (CARBONATE STONE)
0100	401014	387.00	TON		
					SUPERPAVE TYPE B, PG 64-22
0110	401021	637.00	TON		
					SUPERPAVE TYPE BCBC, PG 64-22
0120	601010	41.00	LF		
					REINFORCED CONCRETE PIPE, 12" CLASS III
0130	601140	1.00	EACH		
					REINFORCED CONCRETE FLARED END SECTION, 12"
0140	602100	1.00	EACH		
					DRAINAGE INLET GRATE(S)
0150	602130	1.00	EACH		
					ADJUSTING AND REPAIRING EXISTING DRAINAGE INLET
0160	701012	939.00	LF		
					PCC CURB, TYPE 1-6
0170	705001	3189.00	SF		
					PCC SIDEWALK, 4"
0180	705002	443.00	SF		
					PCC SIDEWALK, 6"
0190	705007	80.00	SF		
					DETECTABLE WARNING SURFACE
0200	705504	400.00	SF		
					BRICK AND/OR BLOCK SIDEWALK
0210	707001	11.00	SY		
					RIPRAP, R-4
0220	727030	190.00	LF		
					FENCE RELOCATION

0230	727031	1.00 EACH	GATE RELOCATION
0240	760010	1197.00 SYIN	PAVEMENT MILLING, BITUMINOUS CONCRETE PAVEMENT
0250	762000	1024.00 LF	SAW CUTTING, BITUMINOUS CONCRETE
0260	762001	66.00 LF	SAW CUTTING, CONCRETE, FULL DEPTH
0270	763000	1.00 LS	INITIAL EXPENSE/DE-MOBILIZATION
0280	763001	1.00 LS	BASELINE SCHEDULE TYPE 1
0290	763002	13.00 EAMO	MONTHLY UPDATE SCHEDULE TYPE 1
0300	763501	1.00 LS	CONSTRUCTION ENGINEERING
0310	763502	1.00 LS	SITE FURNISHING
0320	763504	1.00 LS	SITE WORK
0330	763511	1.00 LS	MAINTENANCE BUILDING
0340	763598	13.00 EAMO	FIELD OFFICE, SPECIAL I
0350	801000	1.00 LS	MAINTENANCE OF TRAFFIC
0360	813001	23360.00 LFDY	TEMPORARY BARRICADES, TYPE III
0370	817002	987.00 SF	PERMANENT PAVEMENT STRIPING, SYMBOL/LEGEND, ALKYD-THERMOPLASTIC
0380	817013	1583.00 LF	PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, WHITE/YELLOW, 5"
0390	817031	138.00 SF	REMOVAL OF PAVEMENT STRIPING
0400	818001	24.00 SF	SUPPLY OF FLAT SHEET ALUMINUM SIGN PANEL, TYPE IV, RETROREFLECTIVE SHEETING
0410	819011	6.00 EACH	GALVANIZED TELESCOPING STEEL SIGN POSTS, 12' X 2", COMPLETE W/ BASEPOSTS AND HARDWARE
0420	819018	10.00 EACH	INSTALLATION OR REMOVAL OF TRAFFIC SIGN(S) ON SINGLE SIGN POST
0430	830001	4.00 EACH	CONDUIT JUNCTION WELL, TYPE 1, 20" X 20" PRECAST CONCRETE
0440	830002	2.00 EACH	CONDUIT JUNCTION WELL, TYPE 4, 20" X 42-1/2" PRECAST CONCRETE
0450	830004	1.00 EACH	CONDUIT JUNCTION WELL, TYPE 7, 36" X 60" PRECAST POLYMER CONCRETE
0460	830008	2.00 EACH	ADJUST OR REPAIR EXISTING CONDUIT JUNCTION WELL

0470	830010	1.00 EACH	REMOVAL OF EXISTING JUNCTION WELL
0480	831513	260.00 LF	PROVIDE AND INSTALL 2" SCHEDULE 80 PVC CONDUIT (TRENCH)
0490	831515	155.00 LF	PROVIDE AND INSTALL 3" SCHEDULE 80 PVC CONDUIT (TRENCH)
0500	831516	150.00 LF	PROVIDE AND INSTALL 4" SCHEDULE 80 PVC CONDUIT (TRENCH)
0510	831523	5.00 LF	PROVIDE AND INSTALL 2" GALVANIZED CONDUIT (TRENCH)
0520	831545	885.00 LF	PROVIDE AND INSTALL 4" HDPE SDR-13.5 CONDUIT (BORE)
0530	831561	15.00 LF	PROVIDE AND INSTALL 1-1/2" SCHEDULE 80 PVC CONDUIT (TRENCH)
0540	832007	2200.00 LF	PROVIDE AND INSTALL 1-CONDUCTOR #4 AWG STRANDED COPPER, TYPE USE-2
0550	834006	3.00 EACH	POLE BASE, TYPE 6
0560	843001	1.00 LS	ELECTRICAL TESTING
0570	850011	3.00 EACH	REMOVAL OF LUMINAIRE
0580	905001	147.00 LF	SILT FENCE
0590	905004	1.00 EACH	INLET SEDIMENT CONTROL, DRAINAGE INLET
0600	907017	104.00 LF	COMPOST FILTER LOGS
0610	908004	3885.00 SY	TOPSOIL, 6" DEPTH
0620	908014	2685.00 SY	PERMANENT GRASS SEEDING, DRY GROUND
0630	908016	1200.00 SY	PERMANENT GRASS SEEDING, SUBDIVISION
0640	908020	3885.00 SY	EROSION CONTROL BLANKET MULCH
0650	908023	4.00 SY	STABILIZED CONSTRUCTION ENTRANCE
0660	911000	1.00 LS	PLANTINGS
0670	911509	400.00 SY	MULCHING

Section 0001 Total

Item Total

\$0.00