

*Ring W. Lardner, P.E.
W. Zachary Crouch, P.E.
Michael E. Wheelleton, AIA, LEED GA
Jason P. Loar, P.E.
Jamie L. Sechler, P.E.
Michael R. Wigley, AIA, LEED AP*

**PORTICO REPAIR
AT
PRICKETT BUILDING
DELAWARE HOSPITAL FOR THE CHRONICALLY ILL
SMYRNA, DELAWARE
DBF #0586B042.H02
AUGUST 19, 2022**

ADDENDUM NO. 2

The following items shall become a part of the contract documents. Contractor must acknowledge receipt of this addendum on the Bid Form. Failure to do so may subject the Bidder to disqualification.

- Item No. 1 Contractor shall price the following alternate (Alternate #2):
- Remove one row of ceiling panels and shore/brace the existing roof.
 - Remove all concrete beams, stonework, and the stone columns (3).
 - Purchase and install new steel columns with fiberglass column wrap, steel beams, wood framing, and EIFS as shown in the attached drawings, S100A and S101A.
- Item No. 2 The contractor is responsible to contact a shoring subcontractor to determine how to shore/brace the roof.
- Item No. 3 The contractor will need to provide Payment and Performance Bonds, see attached.
- Item No. 4 Basis of Design for the fiberglass column wrap is Edon, Tapered Style Tuscan Column cover or equal.
- Item No. 5 Clarification, Note #10, A100: The new column wrap mentioned is the EPS board column wrap with EIFS.
- Item No. 6 A detail regarding the ceiling panel replacement is attached. Each panel size will match existing.

END OF ADDENDUM