



**Gipe Associates, Inc.**  
CONSULTING ENGINEERS

W.O.#: 20050

July 12, 2023

Bryan Williams, AIA  
ABHA Architects  
1621 North Lincoln Street  
Wilmington, Delaware 19806

Project: Cape Henlopen Middle School  
Reference: ASI-032

This ASI forms a part of the contract documents and modified the original bidding documents dated March 18, 2022.

This ASI consists of one (1) page and the attached revised drawings.

**CHANGES TO DRAWINGS:**

1. Sheet EP-111 – FIRST FLOOR PLAN – AREA ‘A’ – POWER  
**REVISE** power for basketball backstops and divider curtain in Gymnasium A111.  
**REVISE** keynotes.  
**DELETE** power for game timers in Girls Locker A117 and Boys Locker A123
2. Sheet E-202 – PART PLANS – ELECTRICAL  
**DELETE** gymnasium control panel in Electrical A113 and associated circuits.
3. Sheet E-302 – DETAILS – ELECTRICAL  
**DELETE** detail 8 for gymnasium equipment control wiring diagram.
4. Sheet E-503 – SCHEDULES – ELECTRICAL  
**DELETE** control panel GCP1 schedule.
5. Sheet E-508 – SCHEDULES – ELECTRICAL  
**REVISE** circuits 1, 3, and 5 in panelboard P1A3 to “SPARE”.  
**REVISE** circuits 38, 40, and 42 in panelboard P1A3 to serve basketball backstops and divider curtain.

**END OF ASI-032**

Enclosures:  
EP-111, E-202, E-302, E-503, E-508