

DELAWARE OFFICE:

2500 WRANGLE HILL ROAD
FOX RUN OFFICE PLAZA, SUITE 110
BEAR, DE 19701

302.832.1652 **PHONE**

302.832.1423 **FAX**

ARCHITECTS

ENGINEERS

FACILITIES SOLUTIONS

ASI No. 1 – Cutting, Patching & Painting

TO : Conventional Builders

FROM : Dan Shurina

DATE : 01/02/2023

REFERENCE : 19121 East Wing HVAC Replacement at DelDOT Admin Bldg

Changes to Scope:

1. Add cutting, patching and painting to facilitate routing of eight (8) new hot water risers from lower level to 1st and 2nd floors.
 - a. No framing is to be included. It may be assumed the work can be performed with existing metal stud framing in place.
 - b. Provide pricing for eight (8) locations on first floor and eight (8) locations on 2nd floor, in coordination with mechanical contractor.
 - c. Paint is to match existing finish per DelDOT standard finish chart provided by SJ.
 - d. The wall is not a fire rated assembly, and new wallboard is to be type-x GWB of matching thickness (5/8" may be assumed for pricing but to be confirmed prior to ordering).

END